

Dublin Airport Apron Re-Grade

Fitzpatrick Contractors are currently working at Dublin Airport undertaking the re-construction of PQ concrete apron as part of the construction of the proposed T2 (Terminal 2).

The works comprise of the break out of existing PQC & DLC and re – construction of 70,000m² of new PQ & DL concrete.

The works are to be completed in (3) three phases and the following phase can only commence once the previous phase has been completed due to the requirement of space by DAA (Dublin Airport Authority) for the parking of planes.

The original programme duration is 41wks which is linked to the commencement of the proposed Pier E on the 19th May 08 (by others).

The Works Package:

- Drainage: installation of 7no interceptors and 1900m of pipe runs (between 2.5 & 4.0m deep).
- 13500m of ducting.
- 1070m of Fuel Main and associated fuel hydrants.
- Installation and upgrade of Aeronautical Ground Lighting (AGL).
- Erection of new High Mast Lighting Towers (HML).
- 70000m² of both PQC & DLC.

The anticipated completion date for the works is Nov 08.

- For more information:
Joe Quirke, E: joe.quirke@fitzpatrick.co.uk



RAF Brize Norton Aircraft Servicing Platform

Fitzpatrick have recently commenced an £9.4m project to construct an additional 18 stands for a new 180,000m² Aircraft Servicing Platform at RAF Brize Norton.

Fitzpatrick have purchased a new state of the art Elba 100 batch plant to batch the 95,000m³ of PQC and Drylean concrete, which will be paved by Fitzpatrick's Gomaco slip form and Vogeles pavers.

- For more information: Joe Quirke,
E: joe.quirke@fitzpatrick.co.uk

Creating: Jobs, Communities, Investment & Sustainable Solutions



Fitzpatrick Contractors Ltd ~ Hertford Road ~ Hoddesdon ~ Hertfordshire ~ EN11 9BX
T: 01992 305000 ~ F: 01992 305001 ~ E: enquiries@fitzpatrick.co.uk

FITZPATRICK

www.fitzpatrick.co.uk

VolkerWessels company